

Advance

ROV and Survey Vessel

Vessel type	CTruk 15m MPC built 2010
Length	15m
Beam	5.80m
Draft	0.75m
Displacement	20,000kg
Max Speed	25knots
Engines	2 X Cummins 600HP @ 2300RPM.
Equipment	SIMRAD/chart plotter X 2; Echo Sounder; VHF X 2. Anchor winch. Tie down points for 3000kg 100KVa Generator. 2000litre fuel tanks and pump with capacity to lift 20m. Class A AIS, SeaMarshall crew finder
Classification	MCA Category 2 for 12 passenger + 2crew
Present location	Orkney